BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2016-17/RD/WORK_INDENT24285

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Improvements to Road and Drains at Kogilu, Ayyappa Enclave in Ward No. 05 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M SATISH	
				In Figures	In Words
1	68.75	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	80.0	Rupees Eighty Only
2	647.96	Removing B.S Slab of Drain and stacking	Sqm	63.0	Rupees Sixty Three Only
3	647.96	Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	78.0	Rupees Seventy Eight Only
4	114.35	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick	Sqm	630.0	Rupees Six Hundred Thirty Only
5	1.9	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5100.0	Rupees Five Thousand One Hundred Only
6	3.51	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	4400.0	Rupees Four Thousand Four Hundred Only
7	2.93	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Sqm	5250.0	Rupees Five Thousand Two Hundred Fifty Only
8	7.65	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications.	Sqm	260.0	Rupees Two Hundred Sixty Only
9	1.04	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5550.0	Rupees Five Thousand Five Hundred Fifty Only
10	6.5	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	100.0	Rupees One Hundred Only
11	2.47	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification.	Cum	6340.0	Rupees Six Thousand Three Hundred Forty Only

Signature of the contractor

15/03

Executive Engineer

15/03

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M SATISH	
				In Figures	In Words
12	0.21	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No.	Qtl	59400.0	Rupees Fifty Nine Thousand Four Hundred Only
13	254.1	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification	Cum	1726.0	Rupees One Thousand Seven Hundred Twenty Six Only
14	1270.5	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity	Sqm	59.0	Rupees Fifty Nine Only
15	31.76	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications.	Cum	6400.0	Rupees Six Thousand Four Hundred Only
16	68.75	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	Cum	72.0	Rupees Seventy Two Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

15/03